REPUBLIC OF THE PHILIPPINES
PUBLIC-PRIVATE PARTNERSHIP CENTER

SUPPLEMENTAL BID BULLETIN NO. 1

Supply, Delivery, Installation, Commissioning, and Testing of Network Device and Security Equipment for Redundancy

This Supplemental Bid Bulletin for the Supply, Delivery, Installation, Commissioning, and Testing of Network Device and Security Equipment for Redundancy is issued to clarify, amend and/or modify certain provisions of the Bidding Documents as a result of the Pre-bid Conference held on September 25, 2017 at PPP Board Room, 8th Floor One Cyberpod Centris EDSA cor. Quezon Avenue, Quezon City:

Specific Page/Section	Query/Issue	PBAC Response/Clarification
Section VII. Technical Specifications Page 70	Brand: Identify the brand of existing Email Security Appliance	• Cisco C170 • Smartnet 8x5, 3 Year • Inbound/Outbound email protection for 160 users, 3 Year • Software bundle (Anti-Spam, Anti-Virus, Outbreak filters, Encryption and Data Leakage Protection) for 160 users, 3 Year • McAfee anti-virus, 3 Year
Page 73	Identify the existing Firewall	• FG-200D • Fortinet 18XGE RJ45 (16XLAN Ports, 2XWAN Ports), 2XGE SFP DMZ Ports • 8x5 Forticare
	One (1) Unit of Firewall Appliance for Redundancy: For the redundancy requirement, we just want to clarify the rest of the technical specifications given, should **FortiGate-200D** be proposed (which is the same as the existing firewall), the technical values given will not be met. Furthermore, these values (specs requirement) will be complied by **FortiGate-201E** but will not be possible for the redundancy	Please refer to the technical specification as a minimum requirement. As stated in the pre-bid conference the device that will be offered is not end-of-life.

	requirement since they are of **different model.**	
Page 74	Identify the existing Core Switch	• Cisco Catalyst 3850-NM-2-10G • 24 Port • Redundant power supply
Page 75	One (1) Unit of Core Switch for Redundancy Referring to "Small Form-factor Pluggable (SFP) Fiber Optic with Transceiver for the uplink or equivalent SFP form". May we validate the **type and quantity of the SFP transceiver** required for the uplink of the Core Switch [Would it be Copper/Single-mode or Fiber/Multimode]	• Transceiver 10G x 2 units • Fiber • Multimode
Page 71	Indicated in Technical Specs Features on page 71 that ESA should be able to support up to 1000 mailboxes just like what's indicated in TOR? Because we think 1000 is too much, for your Mc Afee license, you only purchased 100lics	This is the capability features of the ESA appliance. The existing appliance have 160 users and licenses, 3 Year support.
Page 72	Indicated in Technical Specs Features on page 72 that ESA should integrate with Existing Centralized Management Appliance. But upon questioning it during the pre-bid the technical engineer said that you don't have an existing management appliance	Yes, we do not have an existing Centralized Management Appliance but we have the vlan management for all our appliance.
Section VI. Schedule of Requirements *Items 1,2, and 3* Page 67	Timeline of Items 1 to 3 in the Schedule of Requirements: Within 50 Days upon receipt of Notice to Proceed	**To amend** *"Within 50 Days upon receipt of Notice to Proceed"* **To** *"Within 60 Days upon receipt of Notice to Proceed"*

Item 7 Page 67	Please clarify if 8x5 call and onsite support refers to After Sales Support after equipment complete installation and deployment.	Yes, it is After Sales Support.

For guidance and information of all concerned.

Issued this 29th day of September 2017.

FEROISA FRANCISCA T. CONCORDIA
Chairperson, Bids and Awards Committee